


FE-H31JF4(8)-36C type fiber optic splitter enclosure


1. INTRODUCTION

H31 provides efficient cable connections between outside feeder cable and drop cable in front of FTTX service subscribers. H31 integrates fiber splicing, storage, cable connections and drop to the subscriber line in the closure. It has separated areas for splicing and connectivity. The reason for this separation is to facilitate change without addressing feeder cable line or compromising the splice area.





2. PICTURES





3. SPECIFICATION

Parameter				
General	Size (W x D x H)	329.5*248*144.5		
	Installation	Aerial & Poll mounting	Applicable temperature: -40°C~+90°C	
	Protection Grade	IP 66		
Ports	Cable Entry	Main + Distribution: 2+2		
		Drop (or Patch): 8		
	Cable diameter	Main + Distribution: Φ 7~12		
	(mm)	Drop (or Patch): 3mm		
Capacity	Capacity of core	36 cores		
Splice tray	3 trays	Max. 12 fibers/ tray	Fiber radius of curvature: ≥37.5mm	
Adaptor	8 sets SC adapte	ters max.		
Splitter	1 set 1;16 splitter or 1 set 1:8 splitter or 1 set 1:4 splitter			



4 TEST REPORT

4.1 Vibration test

ltems			
Test Procedure	 Fix the fiber distribution panel on the vibration tester Vibrate for 1 hours with amplitude 1 mm, frequency 10-55-10Hz In 10minutes Check the mechanical damage 		
Requirements	There should be no cracks, fractures and disconnection.		
Test Assembly	[Test Equipment] Vibration Tester→ HI-5050		
Test Result	1. Cracks/fracture/disconnection	None	
	2. Mechanical damage	None	
Judgment	Complied		
Test Procedure	 Put fiber distribution panel in the tester. Thermal cycle: -40 → 0 → 70(relative humidity 80%) (Maintaining 2hr at each Temp.) Temp. rising/falling: 1 °C/min 10 cycling tests (17hr 12min) Check corrosion and mechanical damage. 		
Requirements	 There should be no corrosion There should be no mechanical damage. 		
Test Result	1.Crossion		
	2. Mechanical damage	None	



Test Procedure	Direct the wind horizontally through the water spray such that 1. it impacts the closure on the side. 2. Expose each surface of the closure during 30min. •Rainfall rate: 15cm/hr. (5.8inchs/hr.) •Droplet size: 0.4 ~ 4.5mm (0.016~0.178 inch) •Wind velocity: 31m/s (70mile/h) •Closure Temperatures: At least 10°C greater than the water temperature prior to spraying				
Requirements	1. No presence of water ingress 2. There should be no mechanical damage.				
Test Assembly	50 cm (19.7 inch)				
Test Result	Judgment	PASS			



5. KIT CONTENT

1	Closure body	Cover/middle part/base	1 set
2	Splice tray	Splice tray	1 set
		Mounting kits (Standard kits)	1 set
4	Mounting kits	Wall mounting kits (optional)	1 set
4		Fiber splice tube	24 pcs
	Splice kit bag	Cable tie	2 pcs
	Main cable fixing accessories	Sand paper0#	1 pc
5		M4X10 screws	12 pcs
7	Self-sealing tape	Self-sealing tape	1 roll
8	Sealing rubbers	Sealing rubbers	4 sets

